

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10</u> N R <u>12</u> W	Tyrone Twp. J-10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 NOV - 4 AM 8:37

11504

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Sept. 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-10 1837 GLO Williams & Works Kent Co. Wits. 3" Elm NW 24' Edge large stone W 17.2' Hwy. Culv. N 115.5' 14" Oak W 224.6'
- 1972 LCRC #191 Salisbury Mon. Box' 14" Maple W 224.6' Hwy. Culv. N 115.5' 5' W. of C/L road
- 1986 LCRC #4504 Roosien 1/2" Iron in Mon. Box 10" Hickory N80°E 42.90' 1" Iron Pipe E 33.00' 6" Birch N60°E 44.35' C/L top CMP N15°E 118.9'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/23/99  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-10 Found 1/2" Iron Pipe in Mon. Box (Mon. Box 4" below grade) 5' W. of C/L of road - per witnesses of LCRC #4504.

Said 1/2" Iron Pipe is 0.3' W. and 6.2' N. of intersection of 1/4 lines and agrees with measurements ± by Williams & Works, Roosien, Hackbardt, Glaza, and All Points.

The 1/2" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-10 Set Standard Kent County Monument in place of the 1/2" Iron Pipe. Placed new and smaller Mon. Box inside of old
- Nail & KC Remon. tag SE side 10" Birch N60°E 44.17'
- Nail & KC Remon. tag N. side 18" Hickory N80°E 42.83'
- Top C/L of 1" Iron Pipe East 32.96'
- Cut Nail W. side 12" Birch S55°E 33.75'
- Nail & KC Remon. tag W. side 12" Birch N20°E 87.85'
- C/L top E. end CMP N15°E 118.9'
- C/L N-S asphalt road is 5' East



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 10/28/99