

\$7.00  
\$2.00

MAR 28 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:03

REG. OF DEEDS  
*[Signature]*

11184

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey

T 10N R 12W

Tyrone Twp.

K-2

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2	●	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-2 1837	GLO	Whitcomb	Set Post
	Kent Co. Wits		No information
1984	LCRC #3843	E. Glaza	3/4" Iron Pipe at fence corner.
1989	LCRC #5236	Kolehouse	Set Kent County Monument
1991	LCRC #6022	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 10-21-89 and was recorded per LCRC #5236.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 3/4" Iron he found at a fence corner. Said Iron checks with LCRC #3843.

LCRC #5236		LCRC #6022	
Nail & Remon. tag 14" Maple S45°E	18.95'	Nail & Remon. tag 14" Maple S45°E	18.82'
Nail & Remon. tag 16" Oak S65°W	12.95'	Nail & Remon. tag 18" Oak S65°W	12.98'
Nail & Remon. tag 10" Oak West	22.65'	Nail & Remon. tag 12" Oak S90°W	22.65'
Nail & Remon. tag 8" Poplar N30°E	33.22'	Nail & Remon. tag 8" Poplar N30°E	33.31'
Face of corner fence post West	0.4'	Nail & Remon. tag 30" Oak S25°W	59.13'
		Face of corner fence post West	0.4'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Standard Kent County Monument

Nail & KC Remon. tag S. side 16" Maple	S45°E	18.78'
Nail & KC Remon. tag SE side 20" Oak	S65°W	12.98'
Nail & KC Remon. tag N. side 14" Oak	S90°W	22.65'
Nail & KC Remon. tag SE side 12" Poplar	N30°E	33.27'
Nail & KC Remon. tag E. side 30" Oak	S25°W	59.13'
Face of fence corner post	West	0.4'



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 2/25/99