

\$7.00  
\$2.00

MAR 22 2000

# KENT COUNTY REMONUMENTATION

SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.  
K-3

1. Public Land Survey

T 10N R 12W

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

1999 MAR 24 AM 8:03

REG. OF DEEDS

*[Signature]*

**11185**

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

### A. Description of original monument and accessories and/or subsequent restoration:

K-3	1837	GLO	Whitcomb	Set Post
	1963	Kent Co. Wits		1" Iron
	1971	LCRC #90	Chambers	1 1/2" Iron
	1982	LCRC #3017	Starr	Set Kent County Monument
	1991	LCRC #6023	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 8-2-82 and was recorded per LCRC #3017.

### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 1 1/2" Iron Pipe he found. Said Iron Pipe checks with Kent Co. Wit. and LCRC #90.  
LCRC #3017 LCRC #6023

Nail & Remon. tag 28" Maple S50°E 20.67'	Nail & Remon. tag 30" Maple S50°E 20.62'
Nail & Remon. tag 18" Maple S40°W 30.11'	Nail & Remon. tag Tw. 12" Maple S40°W 30.11'
Nail & Remon. tag 12" Oak West 28.98'	Nail & Remon. tag 15" Oak S90°W 29.00'
Nail & Remon. tag 12" Maple N25°W 27.10'	Nail & Remon. tag 15" Maple N25°W 27.12'
Nail & Remon. tag 10" Maple N20°E 22.73'	Nail & Remon. tag 12" Maple N20°E 22.76'
Nail & Remon. tag 24" Maple N60°E 19.77'	Nail & Remon. tag 24" Maple N60°E 19.79'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Standard Kent County Monument

Nail & KC Remon. tag NE side 32" Maple	S50°E 20.60'
Nail & KC Remon. tag SE side Twin 15" Maple	S40°W 30.07'
Nail & KC Remon. tag S. side 15" Oak	S90°W 29.00'
Nail & KC Remon. tag W. side 15" Maple	N25°W 27.12'
Nail & KC Remon. tag W. side clust. 6"-12" Maple	N20°E 22.78'
Nail & KC Remon. tag N. side 24" stump	N60°E 19.79'



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 2/25/99