

**KENT COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 1999 MAR 24 AM 9:03

REG. OF DEEDS

**11186**

Register of Deeds Stamp & File Number

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10</u> N R <u>12</u> W	Tyrone Twp. K-4
2. Property Controlling in Section	T ___ R ___	_____
3. Miscellaneous Property in Sec.	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Kirk Breitel, in a field survey on Jan. 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 2/25/99  
 CHAIRMAN Randy J. Kolehouse

**A. Description of original monument and accessories and/or subsequent restoration:**

K-4 1837	GLO	Whitcomb	Set Post
1936	Williams & Works		Iron
1963	Kent Co. Wits		1/2" Iron in Mon. Box
1984	LCRC #3883	Kolehouse	Set Kent County Monument in Mon. Box
1991	LCRC #6024	Byl	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 8-11-84 and was recorded per LCRC #3883.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the Iron he found in a Mon. Box. Said Iron checks with Williams & Works information and Kent Co. Wits.  
 LCRC #6024  
 LCRC #3883


Nail & Remon. tag 16" Maple	S75°E	28.00'	Nail & Remon. tag 16" Maple	S75°E	28.02'
Nail & Remon. tag P. Pole	N30°E	78.05'	Nail & Remon. tag P. Pole	N30°E	78.02'
Nail & Remon. tag 12" Pine	N45°W	31.77'	Nail & Remon. tag 12" Pine	N45°W	31.72'
Nail & Remon. tag 8" Oak	S85°W	34.23'	Nail & Remon. tag 10" Oak	S85°W	34.19'
Nail & Remon. tag 14" Oak	S25°W	60.42'	Nail & Remon. tag 16" Oak	S25°W	60.42'

C/L Bt. (Red Pine Dr.) East 1.3'  
 The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-4 Standard Kent County Monument in Mon. Box

Nail & KC Remon. tag S, side 18" Maple	S75°E	28.02'
Nail & KC Remon. tag NW side P. Pole	N30°E	78.04'
Nail & KC Remon. tag W, side 20" Oak	N20°W	47.95'
Nail & KC Remon. tag N, side 12" Oak	S85°W	34.19'
Nail & KC Remon. tag W, side 18" Oak	S25°W	60.45'



Signed by Kirk Breitel  
 Surveyor's Michigan License No. 30077

Date 2/25/99