

REGISTERED
MAY 22 2000
SECTION

KENT COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:03
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

Located In: _____ Corner Code #
Tyrone Twp.
K-6

1. Public Land Survey	T <u>10</u> N R <u>12</u> W	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

11188
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Kirk Breitals, in a field survey on Jan. 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6 1837	GLO	Whitcomb	Set Post
	Kent Co. Wits		No information
1947	Williams & Works		Fence Corner
1979	LCRC #1248	Wickham	Set Concrete Monument by double proportionate measurement
1991	LCRC #5863	Bueche	Set Kent County Monument 1/2 distance NW-SW corners & on fence line

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]
CONCRETE MONUMENT PER LCRC #1248 - INCORRECT

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on _____ and was recorded per LCRC #5863.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche. Said location checks with old Williams & Works information ±.

LCRC #5863	Concrete Monument	North	21.34'
	Nail & Remon. tag SE side 12" Maple	N70°W	24.00'
	Nail & Remon. tag S. side 8" Poplar	N40°E	49.95'
	Nail & Remon. tag N. side 8" Poplar	N55°E	38.76'

Fence corner for fence South & East is North 108°
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Standard Kent County Monument	Concrete Monument (incorrect corner)	North	21.43'
	Nail & KC Remon. tag SE side 12" Maple	N70°W	24.00'
	Nail & KC Remon. tag N. side 24" Willow	S55°E	35.77'
	Nail & KC Remon. tag W. side 30" Poplar	N45°E	95.93'
	Nail & KC Remon. tag E. side P. Pole	N10°E	73.47'
	Nail & KC Remon. tag SW side 12" Maple	N20°W	47.51'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99