

LOONEY & PATTON

RECORDS

RECORDS

RECORDS

\$7.00
\$2.00

MAR 23 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 21 AM 9:03

REG. OFFICERS
[Signature]

For corners in
KENT COUNTY
(County)

Located In: Tyrone Twp.
Corner Code # K-7

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

	T	10N	R	12W	
	T		R		
	T		R		
	T		R		
S	T		R		
S	T		R		
S	T		R		
S	T		R		

11189

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-7	1837	GLO	Whitcomb	Set Post
		Kent Co. Wits		No information
		Willaims & Works		Fence Corner (old records)
1977		Prien & Newhof		Computed corner per double proportionate measurement
1982		Survey	Bueche	Set Capped Iron at fence corner
1991		LCRC #5752	Roosien	Set Kent County Monument

P.A. 345 1900 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Kevin Roosien on 2-15-91 and was recorded per LCRC #5752.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kevin Roosien in place of the Capped Iron (Bueche) he found. Said Capped Iron (Bueche) checks with old Williams & Works information.

LCRC #5752

Nail & Remon. tag SE side 5" Poplar	N45°E	3.91'
Nail & Remon. tag S. side 5" Poplar	East	42.60'
Nail & Remon. tag W. side 8" Poplar	S15°W	34.42'
Nail & Remon. tag E. side 6" Maple	N10°W	49.97'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 Standard Kent County Monument in swamp

Nail & KC Remon. tag SE side 5" Poplar stump	N45°E	3.89'
Nail & KC Remon. tag S. side 5" dead Poplar	East	42.60'
Nail & KC Remon. tag W. side 8" Poplar stump	S15°W	34.42'
Nail & KC Remon. tag E. side 6" Maple stump	N10°W	50.00'



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 2/25/99