

2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey

T 10NR 12W

K-8

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous
Property in Sec.

S ___

T ___ R ___

S ___

T ___ R ___

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 9:03

11190

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 15, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1837	GLO	Whitcomb	Set Post
	Newaygo Eng.		"T" Iron
1983	Survey	Jonker	"T" Iron
1984	LCRC #3882	Kolehouse	Set Kent County Monument
1991	LCRC #6026	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Randy J. Kolehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 8-11-84 and was recorded per LCRC #3882.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the "T" Iron he found. Said "T" Iron checks with Newaygo Eng. and Jonker information.

LCRC #3882		LCRC #6026	
Nail & Remon. tag 10" Oak	S70°E 34.85'	Nail & Remon. tag 12" Oak	S70°E 34.85'
Nail & Remon. tag 18" Pine	S65°W 31.30'	Nail & Remon. tag 20" Pine	S65°W 31.33'
Nail & Remon. tag Tw. 18" Pine	N20°W 67.83'	Nail & Remon. tag Tw. 24" Pine	N20°W 67.80'
Nail & Remon. tag 12" Oak	N30°E 66.17'	Nail & Remon. tag 12" Oak	N30°E 66.14'
Nail & Remon. tag		Nail & Remon. tag P. Pole	S80°E 26.01'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Standard Kent County Monument	
Nail & KC Remon. tag S. side 14" Oak	S70°E 34.88'
Nail & KC Remon. tag S. side 22" Pine	S65°W 31.33'
Nail & KC Remon. tag SW side Twin 28" Pine	N20°W 67.83'
Nail & KC Remon. tag W. side 14" Oak	N30°E 66.14'
Nail & KC Remon. tag N. side P. Pole	S80°E 26.01'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/25/99