

\$7.00
\$2.00

MAY 28 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.
K-9

1. Public Land Survey

T 10N R 12W

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-9 1837	GLO	Whitcomb	Set Post
1936	Kent Co. Wits		Iron
1972	LCRC #194	Salisbury	Iron in Mon. Box
1982	LCRC #3021	Starr	Set Kent County Monument
1991	LCRC #6027	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Thomas Starr

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 8-2-82 and was recorded per LCRC #3021.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 1/2" Iron Pipe he found in a Mon. Box. Said Iron Pipe checks with Kent Co. Wits. and LCRC #194.

LCRC #3021	Nail & Remon. tag 6" Maple S50°W 74.40'
	Nail & Remon. tag 10" Cherry N70°W 95.30'
	Nail & Remon. tag 12" Pine N30°E 97.58'
	Nail & Remon. tag 20" Oak N50°E 82.36'
	Nail & Remon. tag 12" Pine S75°E 167.30'
	Nail & Remon. tag P. Pole S30°E 49.38'
LCRC #6027	Nail & Remon. tag 12" Maple S50°W 74.40'
	Nail & Remon. tag 15" Pine N30°E 97.53'
	Nail & Remon. tag 27" Oak N50°E 82.28'
	Nail & Remon. tag 16" Pine S75°E 167.27'
	Nail & Remon. tag P. Pole S30°E 49.36'
	Cut "X" on conc. culv. N75°W 70.91'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Standard Kent County Monument	
Nail & KC Remon. tag NW side 16" Maple	S50°W 74.43'
Nail & KC Remon. tag W. side 18" Pine	N30°E 97.56'
Nail & KC Remon. tag NW side 32" Oak	N50°E 82.28'
Nail & KC Remon. tag N. side 18" Pine	S75°E 167.27'
Nail & KC Remon. tag W. side P. Pole	S30°E 49.36'
"X" cut on N. end 15" concrete culvert	N75°W 70.91'
3' North of C/L 18 Mile Rd. and 1' West of C/L Red Pine Dr.	



Signed by Kirk Breitels

Date 2/25/99

Surveyor's Michigan License No. 30077