

\$7.00  
\$2.00

JUL 22 2000

# KENT COUNTY REMONUMENTATION

## SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
	Tyrone Twp.	
1. Public Land Survey	T <u>10N</u> R <u>12W</u>	<u>K-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REC. OF DEEDS

*[Handwritten Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 JUL -9 AM 11:20

11260

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitel, in a field survey on June 21, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

### A. Description of original monument and accessories and/or subsequent restoration:

K-12 1837	GLO	Whitcomb	Set Post
1971	Kent Co. Wits		3/4" Iron
1977	LCRC #1101	E. Glaza	3/4" Iron Pipe
1982	LCRC #3025	Starr	Set Kent County Monument
1991	LCRC #6029	Byl	Reset Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/24/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 8-2-82 and was recorded per LCRC #3025.

### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 3/4" Iron Pipe over a "T" iron he found. Both Irons check with Kent Co. Wits. and LCRC #1101.

LCRC #3025	Nail & Remon. tag 12" Ash West	45.68'	LCRC #6029	Nail & Remon. tag 18" Ash	S90°W	45.62'
	Nail & Remon. tag Fence Post N50°W	44.08'		Nail & Remon. tag P. Pole	N40°E	131.72'
	Nail & Remon. tag P. Pole N40°E	131.75'		Nail & Remon. tag P. Pole "	S20°E	211.60'
	Nail & Remon. tag P. Pole S20°E	211.60'		Nail & Remon. tag P. Pole	S20°W	195.22'
	Nail & Remon. tag P. Pole S20°W	195.29'		Nail & Remon. tag top support post of fence	N40°W	46.10'
	NE corner frame garage S40°W	163.04'		NE corner frame garage	S40°W	163.12'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Standard Kent County Monument	Nail & KC Remon. tag S. side 20" Ash	S90°W	45.64'
	Nail & KC Remon. tag W. side P. Pole	N40°E	131.72'
	Nail & KC Remon. tag E. side P. Pole	S20°E	211.64'
	Nail & KC Remon. tag E. side P. Pole	S20°W	195.22'
	Nail & KC Remon. tag top support post of fence	N40°W	46.12'
	1' ± East of C/L N-S asphalt road		
	On C/L tree row West ±		



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 6/24/99