

**SURVEY & REMONUMENTATION**

MAR 08 1999

\$7.00  
\$2.00

SECTION

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 9N R 12W K-1  
T R Common  
T 10N R 12W K-13  
T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1	1837	GLO	Brookfield	Set Post
	1938	Kent Co. Wits		1" Iron
	1971	LCRC #6	Bonnema	1" Iron
	1983	LCRC #3383	Stadt	Set Kent County Monument
	1991	LCRC #6030	Byl	Kent County Monument

P.A. 345 1980 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on 5-5-83 and was recorded per LCRC #3383.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Russell E. Stadt in place of the RR Spike over a 1 1/2" Iron he found. Both check with Kent Co. Wits. and LCRC #6.

LCRC #3383	Nail & Remon. tag P. Pole	N20°W	126.40'	Nail & Remon. tag P. Pole	N20°W	126.36'
	Nail & Remon. tag P. Pole	S40°W	94.05'	Nail & Remon. tag P. Pole	S40°W	94.01'
	Nail & Remon. tag 32" Oak	S15°W	122.37'	Nail & Remon. tag 36" Oak	S15°W	122.37'
	Nail & Remon. tag 36" Maple	S75°E	43.35'	Nail & Remon. tag 36" Maple	S75°E	43.35'
	Nail & Remon. tag T. Pole	N30°E	59.63'	Nail & Remon. tag T. Pole	N30°E	59.58'
				W'yly most cor. of garage (siding)	S25°E	174.11'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Standard Kent County Monument			
Nail & KC Remon. tag E. side P. Pole	N20°W	126.36'	
Nail & KC Remon. tag NW side P. Pole	S40°W	94.07'	
Nail & KC Remon. tag E. side 40" Oak	S15°W	122.21'	
Nail & KC Remon. tag E. side Tele. Pole	N30°E	59.58'	
W'yly most corner of garage (siding)	S25°E	174.25'	



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

10485

Register of Deeds Stamp & File Number