

SURVEY & RECONSTRUCTION

MAY 22 2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 NOV -4 AM 8:37

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 10N R 12W	Tyrone Twp. L-1
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

11507
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Record Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-1 1837	GLO	Whitcomb	Not Set
1909	William & Works		Found 2 old wood stakes and stones - jog 169.5'
1973	LCRC #375	Bonnema	Set 3/4" Solid Rod on Twp. Line - jog 272'
1985	LCRC #4378	Ochs	Set Kent County Monument on Twp. Line
1991	LCRC #6031	Byl	Kent County Monument

P.A. 345 1999 KENT COUNTY
PEER APPROVED 9/23/99
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 12-11-85 and was recorded per LCRC #4378.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set on Twp. Line by Norman L. Ochs per 1909 Williams & Works information. Corner per LCRC #375 was determined to be incorrect	LCRC #4378	LCRC #6031
Spike in 6" Elm	N50°W 39.51'	Nail & Remon. tag 8" Elm N50°W 39.51'
Face of 2" Basswood	N05°E 19.32'	Face of 3" Basswood N05°E 19.25'
Spike in 8" Basswood	S10°W 46.16'	Nail & Remon. tag 10" Basswood S10°W 43.11'
Spike in 6" Swamp Oak	S10°E 42.22'	Nail & Remon. tag 8" Swamp Oak S10°E 42.20'
SE cor. Sec. 36-11-12	East 169.5'	Cast Iron Mon. (SE cor. Sec. 36-11-12) N90°E 169.40'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument	S10°W	43.15'
Nail & KC Remon. tag E. side 15" Basswood	S10°E	42.26'
Nail & KC Remon. tag W. side 12" Swamp Oak	N75°E	75.98'
Nail & KC Remon. tag S. side 8" Basswood	N50°W	67.90'
Nail & KC Remon. tag S. side P. Pole	North	32.97'
Capped Rerod (Exxel)	East	169.48'
SE cor. Sec. 36-11-12 (Newaygo Co. Mon.)		



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 10/28/99