

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FILE #

93 SEP 13 PM 2:00

W. J. ...
 REG. OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kent
 (County)

Located In:

TYRONE TWP.
 Corner Code 11

1. Public Land Survey	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	1	T	10N	R 12W L-2
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____
4. Lot No.	Recorded Plat _____				
5. Private Claims	_____				

6843

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Douglas W. Bonnema in a field survey on July 26, 1993
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Williams & Works records of 1895 (FN 12-90) show the point being set midway and on line between E & W 1/4 corners. Williams & Works used again in 1916 to do a petition survey of all of SE 1/4 and SW 1/4 of Section 1. They show distance of 2669.0 feet to the E & W 1/4 corners. Exxel Engineering found this stake & witnessed in 1973 (see L.C.R.C. #375).

B. Description of corrier evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron per L.C.R.C. #375. This has also been accepted and used by Nedervand Assoc., C.S. Hay in recent years, and was approved at a meeting of Kent County Surveyors peer group on July 29, 1993, even though it is approximately 41 feet west of true position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Replaced 1" iron with Kent County Mon. (4"x30" Harrison) Top 6" below surface

Nail & tag in W sde 26" Oak S10°W 56.10'	S 1/4 Cor., S00°30'34"W 2736.36'
Nail & tag in SE sde tw. 24" Oak S5 61.98'	W 1/4 Cor., N88°30'20"W 2654.40'
Nail & tag in SW sde P. Pole N45°W 51.52'	N 1/4 Cor., N02°10'01"E 2961.50'
Nail & tag in NW sde 14" Walnut N31°E 31.76'	E 1/4 Cor., S88°37'45"E 2666.29'
Nail & tag in NW sde 32" Walnut N70°E 69.93'	
C/L E-W gravel North 1'+	

Signed by Douglas W. Bonnema
 Surveyor's Michigan License No. 12579

Date September 7, 1993

