

\$7.00
\$2.00

1999 MAR 24 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:03

REC. OF DEEDS
[Signature]

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

Tyrone Twp.
L-9

1. Public Land Survey

T 10N R 12W
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

11198

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 21, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-9 1837	GLO	Whitcomb	Set Post
1985	LCRC #4313	Bissell	Set Concrete Monument
1986	LCRC #4454	Kolehouse	Found Concrete Monument with DNR Cap at mid-point of mile
1991	LCRC #6035	Byl	Concrete Monument with DNR Cap

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group as monumented (Concrete Monument with DNR Cap) presented by Randy J. Kolehouse on 4-5-86 and was recorded per LCRC #4454.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found Concrete Monument with DNR Cap per witnesses from above LCRC as found and presented by Randy Kolehouse. Said Concrete Monument with DNR Cap checks with LCRC #4313.	LCRC #4313	LCRC #6035
Nail & DNR tag Tri. 12" Oak N29°E 36.75'		Nail & Remon. tag Tri. 12" Oak N29°E 36.71'
Nail & DNR tag 18" Oak S80°E 43.50'		Nail & Remon. tag 18" Oak S80°E 43.50'
Nail & DNR tag 12" Oak S10°W 35.19'		Nail & DNR tag 12" Oak S10°W 35.19'
Nail & tag 16" Cherry S83°W 52.02'		Nail & Remon. tag 16" Cherry S83°W 51.95'
C/L 18 Mile Road is North 16' m/l		Nail & Remon. tag 12" Pine N15°W 66.24'
		Nail & Remon. tag 12" Cherry S60°E 36.04'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Concrete Monument with DNR Cap	
Nail & KC Remon. tag W. side Tri. 15" Oak	N29°E 36.73'
Nail & KC Remon. tag N. side 22" Oak	S80°E 43.50'
Nail & DNR tag W. side 14" Oak	S10°W 35.19'
Nail & KC Remon. tag N. side 18" Cherry	S83°W 51.95'
Nail & KC Remon. tag W. side 14" Pine	N15°W 66.27'
C/L 18 Mile Rd. (gravel) is North 16' ±	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99