

7.00
\$2.00

1997 2 2 2001

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

- 1. Public Land Survey

T <u>10N</u> R <u>12W</u>	<u>M-8 Tyrone Twp.</u>
T _____ R _____	<u>Common</u>
T <u>10N</u> R <u>11W</u>	<u>A-8 Solon Twp.</u>
T _____ R _____	_____
- 2. Property Controlling in Section

S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
- 3. Miscellaneous Property in Sec.

S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on May 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 1837	GLO	Brookfield	Set Post
	Kent Co. Wits		2" Iron
1980	LCRC #1413	Bissell	1 1/2" Pipe - raised with 120d Nail
1986	LCRC #4457	Kolehouse	Set Kent County Monument
1991	LCRC #6003	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 6/24/99
 CHAIRMAN Randy J. Kolehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 4-5-86 and was recorded per LCRC #4457.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found BROKEN Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 120d Nail over an Iron he found. Both check with Kent Co. Wits. and LCRC #1413.

LCRC #4457	LCRC #6003		
Nail & DNR tag 14" Ash	S28°W 55.92'	Nail & DNR tag 18" Ash	S28°W 55.95'
Nail & Remon. tag 16" Oak	S84°W 25.97'	Nail & Remon. tag 18" Oak	S84°W 25.93'
Nail & Remon. tag 8" Twin Oak	S45°E 43.38'	Nail & Remon. tag 12" Twin Oak	S45°E 43.33'
60d Nail Tri. 12" Oak	N21°W 49.60'	60d Nail Tri. 10"-18" Oak	N21°W 49.57'
60d Nail 16" Oak	S23°E 52.55'	60d Nail 18" Oak	S23°E 52.55'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Removed and Reset Standard Kent County Monument

Nail & DNR tag E. side 20" Ash	S28°W 55.95'
Nail & KC Remon. tag N. side 22" Oak	S84°W 25.93'
Nail & KC Remon. tag N. side 12" Twin Oak	S45°E 43.33'
Nail & KC Remon. tag E. side Tri. 10"-18" Oak	N21°W 49.57'
Nail & KC Remon. tag W. side 22" Oak	S23°E 52.52'

In C/L N-S gravel road ±
 On N. edge of wood line to East ±



Signed by [Signature]
 Surveyor's Michigan License No. 30077

Date 6/24/99

REGISTERED
 RECEIVED FROM RECORDS
 1999 JUN -9 AM 11:20
 11261
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													