

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY
(County)

| | | |
|---------------|-------------|--|
| Located In: | Tyrone Twp. | |
| Corner Code # | M-9 | |
| | Common with | |
| | A-9 Selon | |
| | T10N R 12W | |
| | T R | |
| | T10N R 11W | |
| | T R | |
| | T R | |
| | T R | |
| | T R | |
| | T R | |

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

1999 MAR 24 AM 8:04

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

REG. OF DEEDS

11205

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 25, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|----------|---------------|------------|--------------------------|
| M-9 1837 | GLO | Brookfield | Set Post |
| | Kent Co. Wits | | 1" Iron |
| 1980 | LCRC #1411 | Bissell | 1" Iron |
| 1983 | LCRC #3247 | Byl | Set Kent County Monument |
| 1991 | LCRC #6045 | Byl | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 2-28-83 and was recorded per LCRC #3247.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1 1/2" Iron Pipe he found. Said Iron Pipe checks with Kent Co. Wit. and LCRC #1411.

| | | | |
|--------------------------------|--------------|--------------------------------|--------------|
| LCRC #3247 | | LCRC #6045 | |
| Nail & Remon. tag 8" Oak | S30°W 59.87' | Nail & Remon. tag 10" Oak | S40°W 69.88' |
| Nail & Remon. tag 12" Pine | N45°W 56.60' | Nail & Remon. tag 14" Pine | N45°W 56.63' |
| Nail & Remon. tag 10" Oak | N55°E 78.94' | Nail & Remon. tag 12" Oak | N55°E 78.94' |
| Nail & Remon. tag 10" Twin Oak | S45°E 51.35' | Nail & Remon. tag 12" Twin Oak | S45°E 51.35' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Standard Kent County Monument

| | |
|---|--------------|
| Nail & KC Remon. tag NE side 14" Pine | N55°W 73.96' |
| Nail & KC Remon. tag SE side 16" Oak | S50°W 62.54' |
| Nail & KC Remon. tag S. side 14" Oak | N55°E 78.96' |
| Nail & KC Remon. tag N. side 12" Twin Oak | S45°E 51.33' |



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99