

MAY 22 2000

\$7.00  
\$2.00

SECTION

### KENT COUNTY REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:06

REG. OF DEEDS  
*[Signature]*

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 10NR 12W      M-10 Tyrone Twp.  
    T              Common  
    ~~T 10NR 11W~~      ~~A-10 Solon Twp?~~  
    T              \_\_\_\_\_
- 2. Property Controlling      S              \_\_\_\_\_  
    in Section                    S              \_\_\_\_\_
- 3. Miscellaneous            S              \_\_\_\_\_  
    Property in Sec.            S              \_\_\_\_\_

11206

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Jan. 15, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- |           |               |            |                                      |
|-----------|---------------|------------|--------------------------------------|
| M-10 1837 | GLO           | Brookfield | Set Post                             |
|           | Kent Co. Wits |            | 1" Iron                              |
| 1983      | LCRC #3253    | Hackbardt  | 1" Solid Iron                        |
| 1985      | LCRC #4315    | Bissell    | 1" Iron in Mon. Box                  |
| 1986      | LCRC #4458    | Kolehouse  | Set Kent County Monument in Mon. Box |
| 1991      | LCRC #6046    | Byl        | Kent County Monument in Mon. Box     |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 4-5-86 and was recorded per LCRC #4458.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- M-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Solid Iron he found in a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #3253 & #4315.
- |            |   |            |   |
|------------|---|------------|---|
| LCRC #4458 | Nail & Remon. tag 12" Willow S40°W 29.62' | LCRC #6046 | Nail & Remon. tag 14" Willow S40°W 29.42' |
|            | Nail & Remon. tag 12" Poplar N20°W 83.21' |            | Nail & Remon. tag 20" Poplar N20°W 83.14' |
|            | E. end 15" CMP N20°E 84.90'               |            | C/L top E. end 18" CMP N20°E 85.60'       |
|            | E. end 15" CMP S20°E 64.3'                |            | C/L top E. end 24" CMP S20°E 65.40'       |
|            |   |            | C/L top MBT Pedestal S60°E 56.48'         |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10 Standard Kent County Monument in Mon. Box
- |   |              |
|---|--------------|
| Nail & KC Remon. tag SE side 24" Willow | S40°W 29.01' |
| Nail & KC Remon. tag E. side 24" Poplar | N20°W 83.12' |
| C/L top East end 18" CMP                | N20°E 85.60' |
| C/L top East end 24" CMP                | S20°E 65.40' |
| C/L top of Ameritech Pedestal (leaning) | S60°E 57.2'  |



Signed by *[Signature]*  
Surveyor's Michigan License No. 30077

Date 2/20/99