

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 57 N.R. 31 W


THAYER LAKE ACCESS Keweenaw COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 28-29-32-33

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/7/65

WITNESSES TO CORNER..... 20" Y. Birch (S29 NBT), N 56° W, 15 Lks.



8" Soft Maple (S32 NBT), S 30° W, 14 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner replaced from one W. Pine Bearing tree - S 38° W, 28 Lks. Stump cut 6' high, burnt and rotted. Found some scribe marks high on the stump. Found roots and fragments of a W. Pine bearing N 32° W, 28 Lks; this is on edge of bulldozed road. Corner lies 50 lks. West of road and 90 Lks. South of fork in road.

SURVEYOR'S SEAL

*Billy D. Buckler*

SIGNED Billy D. Buckler DATE 3/24/1966  
REGISTERED LAND SURVEYOR