

MAR 29 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Keweenaw County Located in: Corner Code #

1. Public Land Survey		T57N R29W	A1
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	
4. Lot No.			Recorded Plat
5. Private Claims			

REGISTER'S OFFICE } SS  
County of Keweenaw }  
Received for Record, the 12<sup>th</sup>  
day of March A. D. 1999  
at 12:00 o'clock P. M., and Recorded  
in Liber 1 of LCR  
on page 201  
*Marilyn Wengert*  
Register of Deeds  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1	•												
2		6		5		4		3		2			
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A1: NW Corner Section 6: From original notes: East on South side of Sec. 36, T58N, R30W; 80.00 Set post Corner to Townships 57 & 58 North between Ranges 29 & 30 West. No evidence of original corner or accessories found.

Ratified by Peer Group  
In accordance with P.A. 345  
Co. Rep. *James M. ...*  
Date 12/3/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A1: NW Corner Section 6: Found 1 1/4" pipe as recorded by J. I. Haataja, P.S. 19833 in Liber 1 of L.C.R.C., Page 82. Witnesses of said record: 12" Maple N37°E 20.10'; 12" Maple N86°E 25.58'; 8" Maple S43°E 50.55'; P.P. South 14.78'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A1: Replaced 1 1/4" pipe with Brass Cap stamped for corner, 2" A.G.  
Witnesses (checked):  
13" H. Maple N35°E 20.08'  
12" Maple stump N82°E 25.55'  
7" Maple stump S47°E 50.75'  
Util. Pole S02°E 14.77'

New Witnesses:  
9" H. Maple S33°E 43.08'  
7" Ironwood S60°W 66.03'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by *Steven C. Hein*

Date 3/10/99

Surveyor's Michigan License No. 32336