

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Keweenaw County

Located in:

Corner Code #

- 1. Public Land Survey T57N R30W
T57N R30W
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

A1
B1

REGISTER'S OFFICE } SS
County of Keweenaw }
Received for Record, the 4th
day of December A. D. 1998
at 1:00 o'clock A.M., and Recorded
in Liber 1 of LCR
on page 190
Marilyn Wergquist
Register of Deeds
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid with columns A-M and rows 1-13. A dot is marked at the intersection of column B and row 1.

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A1: NW Corner Section 6: From original notes: North on East side of Sec. 1, T57N, R31W; 80.00 Set post Corner to Townships 57 & 58 N. between Ranges 30 & 31 West: Y. Birch 14 N68E 15 lks.; Sugar 10 S53W 12 lks. No evidence of original corner or accessories.

B1: N1/4 Corner Section 6: Not set in original survey.

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. Kenneth H. ...
Date 12/3/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A1: NW Corner Section 6: Found 1" square pin in concrete as recorded by J. I. Haataja, P.S. 19833 in Liber 1 of L.C.R.C., Page 58. Witnesses of said record: 10" Maple N65°E 8.69'; 10" Maple N26°E 16.71'; 10" Maple N75°W 26.15'; 5" Ironwood S38°W 24.17'

B1: N1/4 Corner Section 6: Having found the recorded Northwest and Northeast Corners of the Township, all the GLO corners between were set on a true parallel of latitude established by using the secant method. Quarter corners were established satisfying the proportional area measurements as shown on the original Township Plat. Positions fit well with found evidence. (Note: 5" Sq. Cedar post used by Wiedenhoefler and Noblet as a common 1/4 corner between Sections 6 & 31 is 17.5' South of the computed position for the S1/4 Cor. Section 31, T58N-R30W).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A1: Accepted 1" Square pin in concrete, No Brass Cap set
Witnesses(as recorded)
10" Maple N65°E 8.69'
10" Maple N26°E 16.71'
10" Maple N75°W 26.15'
5" Ironwood S38°W 24.17'

B1: Set 4" Brass Cap stamped for corner on 1" pipe, 10" A.G.,
Witnesses:
7" H. Maple N63°E 23.22'
13" Oak S54°E 15.31'
5" H. Maple S35°W 15.30'
10" Oak N19°W 14.48'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein

Date 11/14/98

Surveyor's Michigan License No. 32336