

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 SECTION

For corners in

Keweenaw County Located in: Corner Code #
 1. Public Land Survey T57N R30W (B3) ✓
 T57N R30W MC2 E2-E3
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 4. Lot No. , Recorded Plat
 5. Private Claims

REGISTER'S OFFICE } SS
 County of Keweenaw }
 Received for Record, the 4th
 day of December A. D. 1998
 at 11:00 o'clock A. M., and Recorded
 in Liber. 1 of LCR
 on page 189
 Maily Wikquist
 Register of Deeds
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3		2		1
3					MC 2								
4	7			8		9			10		11		12
5													
6	18			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B3: S1/4 Corner Section 6: From original notes: East corrected on true line between Sections 6 & 7; 39.90 Set qr. Section post; Fir 9 S73W 14; Sugar 14 N78E 14. No evidence of original corner or accessories found.

MC2 E2-E3: Meander Cor. between Secs. 4 & 5: From original notes: North between Sections 4 & 5; 24.65 Over Lake The corner of Sections 4, 5, 8 & 9 being in Lake. Cedar 12 for Meander Corner; Cedar 12 S54W 12. No evidence of original corner or accessories found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B3: S1/4 Cor. Section 6: Found 6" squared Ironwood at approximate corner. Position fits reasonably well with split of South line of Section 6. Set 1/4 Corner midway between found SW and SE Corners of Section 6

MC2 E2-E3: Meander Cor. Between Secs. 4 & 5: Found 1 1/4" pipe w/ mushroomed top used and accepted as M.C. in previous surveys. Found witness(P.S. 24591): 8" W. Ash N21°W 15.62'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B3: Set 4" Brass Cap stamped for corner on 1" pipe on NW edge old stump

Witnesses:

8" Balsam North 12.56'
 13" H. Maple N64°E 24.91'
 16" R. Maple S01°E 24.50'
 15" Birch N70°W 19.96'

MC2 E2-E3: Replace 1 1/4" pipe with 4" Brass Cap stamped for corner on 1" pipe

Witnesses:

8" W. Ash N21°W 15.62'
 18" H. Maple N50°E 15.91'
 16" H. Maple N87°W 56.40'
 Nail & tag in No. wall of boathouse South 2.18'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein

Date 11/14/98

Surveyor's Michigan License No. 32336