

SURVEY & REMONUMENTATION

NOV 23 1999

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
Keweenaw

(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 57N | R | 30W | E2 ✓ |
| | T | 57N | R | 30W | C2 |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTER'S OFFICE }
County of Keweenaw } SS 12th
Received for Record, the 12th
day of November A.D. 1996
at 9:00 o'clock A.M., and Recorded
in Liber 1 of LCR
on page 146
Manly W. Bergquist
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5	•	4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Steven C. Hein, in a field survey on June 28, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 (E-2) From Original Notes: 40.00 Set qr. Section post; Sugar 8 N9W 32; do 12 S83E 13: No evidence of original corner or accessories.
 (C-2) From Original Notes: 40.00 Set qr. Section post; Yellow Birch 9 S26W 17; Black Oak 16 N41E 20: No evidence of original corner or accessories.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (E-2) Found 1" pin with 7" sq. post w/tag 3.5' North of corner. Witnesses of record: 2" H. Maple East 15.19'; 10' Oak S07E 5.90'; Found two Witnesses with tag #19833 - 15" Oak N40E 10.66'; 13" H. Maple S88W 51.75'
 (C-2) Found 1"x2" stake w/3" sq. post, New al. tag on 11" R. Maple to West. Remains of old location poster on 14" H. Maple to NW. No apparent witnesses.

**Ratified by Peer Group
In accordance with P.A. 345**
 Co. Rep. James McLaughlin
 Date 10/15/96

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|---|---|
| (E-2) Accepted location of 1" pin,
Replaced with 4" Remon. Brass Cap
stamped for corner
Witnesses:
(new) 12" Oak S09E 6.25'
13" H. Maple S88W 51.75'
(new) 8" H. Maple S44E 19.75'
15" Oak N40E 10.66'
Note: New wit. have tag #32336 | (C-2) Accepted location of stake,
Replaced with 4" Remon. Brass Cap
stamped for corner
Witnesses:
8" H. Maple N35E 30.22'
13" R. Maple S80E 4.94'
10" R. Maple S47W 13.17'
7" R. Maple N44W 11.45'
Note: Wit. have tag #32336 |
|---|---|



Signed by Steven C. Hein Date SEPTEMBER 13, 1996
 Surveyor's Michigan License No. 32336