

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw County	Located in:	Corner Code #
1. Public Land Survey	T57N R30W	E1
	T57N R30W	F1 ✓
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

REGISTER'S OFFICE } SECTION
 County of Keweenaw } SS
 Received for Record, the 4th
 day of December A. D. 1998
 at 11:00 o'clock A. M., and Recorded
 in Liber 1 of LCR
 on page 192
Maile Wierquist
 Register of Deeds
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E1: Corner between Sections 4 & 5: From original notes: North between Sections 4 & 5: 80.70 Intersected South boundary of Township 58 North 2.48 East of Corner of Sections 32 & 33. Lynn 20 S28W 10; Sugar 12 S48E 27. No evidence of original corner or accessories found.

F1: N1/4 Corner Section 4: Not set in original survey.

Ratified by Peer Group
 In accordance with P.A. 345
 Co. Rep. James W. Hult
 Date 12/3/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E1: Corner between Sections 4 & 5: Having found the recorded Northwest and Northeast Corners of the Township, all the GLO corners between were set on a true parallel of latitude established by using the secant Method. Position fits well with found evidence.

F1: N1/4 Corner Section 4: Having found the recorded Northwest and Northeast Corners of the Township, all the GLO corners between were set on a true parallel of latitude established by using the secant method. Quarter corners were established satisfying the proportional area measurements as shown on the original Township Plat. Positions fit well with found evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E1: Set 4" Brass Cap stamped for corner on 1" pipe, 13" A.G., 8' No. of Power line
 Witnesses:
 16" Oak N03°E 24.31'
 17" H. Maple S34°E 43.92'
 10" H. Maple S20°W 49.67'
 Util. Pole S85°W 49.67'

F1: Set 4" Brass Cap stamped for corner on 1" pipe, 5" A.G., 9' No. of Power line
 Witnesses:
 14" H. Maple N29°E 48.41'
 7" H. Maple S31°E 57.37'
 6" H. Maple twin S35°W 63.18'
 4" Ironwood N09°W 37.48'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein Date 11/14/98
 Surveyor's Michigan License No. 32336