

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Keweenaw County

Located in:

Corner Code #

1. Public Land Survey

T57N R30W

T57N R30W

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

K1
L1

REGISTER'S OFFICE }
County of Keweenaw }
Received for Record, the 4th
day of December A. D. 1998
at 11:00'clock A.M., and Recorded
in Liber 1 of LCR
on page 195
Marilyn Wenquist
Register of Deeds
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K1: Corner between Sections 1 & 2: From original notes: North between Sections 1 & 2: 80.18 Intersected South boundary 1.64 East of Corner of Sections 35 & 36. Set post corner of Secs. 1 & 2; Lynn 14 S34W 9; Yellow Birch 14 S16E 35; Noevidence of original corner or accessories found.

L1: N1/4 Corner Section 1: Not set in original survey.

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. James M. Dunkel
Date 12/3/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K1: Corner between Sections 1 & 2: Having found the recorded Northwest and Northeast Corners of the Township, all the GLO corners between were set on a true parallel of latitude established by using the secant Method. Position fits well with found evidence.

L1: N1/4 Corner Section 1: Having found the recorded Northwest and Northeast Corners of the Township, all the GLO corners between were set on a true parallel of latitude established by using the secant method. Quarter corners were established satisfying the proportional area measurements as shown on the original Township Plat. Positions fit well with found evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K1: Set 4" Brass Cap stamped for corner on 1" pipe, 7" A.G., 9" No. of Power line
Witnesses:
9" H. Maple N48°E 40.55'
4" H. Maple S35°E 79.50'
10" Balsam S35°W 57.65'
13" H. Maple N38°W 50.00'

L1: Set 4" Brass Cap stamped for corner on 1" pipe, 9" A.G., 12' No. of Power line
Witnesses:
14" H. Maple N51°E 53.13'
3" H. Maple S28°E 49.92'
9" Oak S25°W 53.46'
7" Balsam N54°W 35.17'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein

Date 11/14/98

Surveyor's Michigan License No. 32336