

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw
(County)

Located In:

Corner Code ≠

- | | | | |
|------------------------------------|---------------------------|------------|-------|
| 1. Public Land Survey | T <u>57N</u> R <u>32W</u> | <u>A-3</u> | |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |

REGISTER'S OFFICE }
County of Keweenaw } SS
Received for Record, the 15th
day of December A.D. 1994
at 3:00 o'clock P.M., and Recorded
in Liber 1 of LCR
on page 120
Manly W. J. ...
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John I. Haataja, in a field survey on June 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 A-3 Sec. Corner 6 & 7, T57N-R32W and 1 & 12, T57N-R33W
 Orig. Notes: Wood Post for corner.
 Spruce 6" S 80° W 29 lks.
 Spruce 6" N 7° E 16 lks.
 Keweenaw Land Association records show corner as 10" Aspen with location tag dated 1974.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-3 Sec. Corner 6 & 7, T57N-R32W and 1 & 12, T57N-R33W
 Found location tag on 10" Aspen with lines blazed in three directions. Restored corner at 10" Aspen tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-3 Sec. Corner 6 & 7, T57N-R32W and 1 & 12, T57N-R33W
 Set 1" iron pipe with brass cap as a careful and faithful perpetuation of the position of the original corner.
 12" Poplar South 1.18'
 10" Poplar N 51° E 17.16'
 12" W. Birch N 1° W 29.40'
 5" H. Maple S 80° W 16.74'

Ratified by Peer Group
 In accordance with P.A. 345
 Co. Rep. *James M. ...*
 Date 11/16/94



Signed by *John I. Haataja* Date November 23, 1994
 Surveyor's Michigan License No. 19833