

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Keweenaw
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>57N</u> | R | <u>32W</u> | <u>C-1</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

REGISTER'S OFFICE }
County of Keweenaw } SS
Received for Record, the 15th
day of December A.D. 1994
at 3:00 o'clock P.M., and Recorded
in Liber 1 of LCR
on page 118
Marilyn Teague
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, John I. Haataja, in a field survey on October 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-1 Northeast Corner of Section 6, T57N-R32W
Original Notes: Wood Post.
Sugar 8" N 69° E 15 lks.
Fir 8" N 36° W 40 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-1 Northeast Corner of Section 6, T57N-R32W
No trace of original post.
Re-established corner from natural feature calls and old line blazes.

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. *[Signature]*
Date 11/16/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1 Northeast Corner of Section 6, T57N-R32W
Set a 1" pipe with brass cap as a careful and faithful re-establishment of the position of the original corner.
6" R. Maple N 57° E 6.03'
14" H. Maple S 68° E 17.82'
5" H. Maple S 16° E 10.61'
6" H. Maple N 87° W 19.76'



Signed by *[Signature]* Date November 22, 1994
Surveyor's Michigan License No. 19833