

**SURVEY &
REMONUMENTATION**

OCT 08 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KEWEENAW (County) Located in: _____ Corner Code # _____

1. Public Land Survey	T <u>57N</u>	R <u>32W</u>	<u>C-12</u>
	T <u>57N</u>	R <u>32W</u>	<u>C-13</u> ✓
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER'S OFFICE
County of Keweenaw } SS
Received for Record, the 29th
day of July A.D. 1997
at 10:00 o'clock A.M., and Recorded
in Liber. 1 of LCR
on page 168
Manly Stewart
Register of Deeds

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. W. CRAMPTON, in a field survey on MAY 30, 19 85
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

- NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**
- A. Description of original monument and accessories and/or subsequent restoration:
C-12 WEST 1/4 CORNER-SET POST-
C-13 SOUTHWEST CORNER-SET POST-SUGAR 12 N18E 18, CEDAR 12 N55W 34.

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. James M. Hulshel
Date 7/29/97

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-12 WEST 1/4 CORNER-1 1/2" IRON PIPE FOUND AND SET WITH 4" BRASS CAP.
C-13 SOUTHWEST CORNER-1" IRON PIN IN CONCRETE FOUND AND SET WITH 4" BRASS CAP.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-12 THE 1 1/2" IRON PIPE WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO: 18" MAPLE TREE N63 W 61.2', 5" OAK TREE S65 W 44.97', 4" MAPLE TREE S48 E 46.62', 28" MAPLE TREE S9 W 60.27'.
C-13 THE 1" IRON PIN WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO: 4" CEDAR TREE N16 W 55.18', 4" ASPEN TREE S88 E 28.4', 8" PINE TREE S50 E 27.16', 4" CEDAR TREE S13 W 17.0', EAST 11.89' TO NORTHEAST CORNER SECTION 6, T56N, R32W.

Signed by Robert W. Crampton Date July 22, 1997
 Surveyor's Michigan License No. 24591