

**SURVEY &  
REMONUMENTATION**

**OCT 08 1997**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
KEWEENAW  
(County)

Located In:

Corner Code #

- |   |   |            |   |            |             |
|---|---|------------|---|------------|-------------|
| 1. Public Land Survey                   | T | <u>57N</u> | R | <u>32W</u> | <u>D-11</u> |
|   | T |            | R |            |             |
|   | T |            | R |            |             |
|   | T |            | R |            |             |
| 2. Property Controlling<br>in Section   | S |            | T |            | R           |
|   | S |            | T |            | R           |
| 3. Miscellaneous<br>Property in Section | S |            | T |            | R           |
|   | S |            | T |            | R           |
| 4. Lot No. _____, Recorded Plat _____   |   |            |   |            |             |
| 5. Private Claims _____                 |   |            |   |            |             |

REGISTER'S OFFICE }  
County of Keweenaw } SS  
Received for Record, the 29<sup>th</sup>  
day of July A.D. 1997  
at 10:00 o'clock A. M., and Recorded  
in Liber 1 of LCR  
on page 169  
Robert W. Crampton  
Register of Deeds

Register of Deeds Stamp & File Number

I, R.W. CRAMPTON, in a field survey on SEPTEMBER 21, 1981,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found  
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
D-11 WOODEN POST SET IN 1846 BY SAMUEL W. HILL

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
D-11 FOUND 1 1/4" IRON PIPE AS INDICATED ON AHMEEK MINING COMPANY SURFACE MAP  
DATED SEPTEMBER 1913, AND AS SHOWN ON PLAT OF VILLAGE OF AHMEEK AS RECORDED  
BY J. HAATAJA LIBER 1, PAGE 28, LCR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
D-11 THE 1 1/4" IRON PIPE AS 1/4 CORNER SET WITH 4" BRASS CAP WAS WITNESSED WITH  
SURVEY TAG NAILED TO: 6" CEDAR TREE N52 W, 24.83', 3" CEDAR TREE N21 W 17.32',  
7" CEDAR TREE N77 E 44.35', 3" BASSWOOD TREE S50 W 14.08', MARK ON SOUTH SIDE  
WATER SHUT OFF, S40 W 12.64'.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Ratified by Peer Group  
In accordance with P.A. 345  
Co. Rep. James M. Leibel  
Date 7/28/97



Signed by Robert W. Crampton  
Surveyor's Michigan License No. 24591

Date July 22, 1997