

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KEWEENAW - REMON
(County)

Located In:

Corner Code #

REGISTER'S OFFICE

County of Keweenaw } SS

Received for Record, the 8th
day of November A.D. 1996
at 11:00 o'clock A. M., and Recorded
in Liber 1 of LCR
on page 141
Roberta Rosenberger, Deputy
Register of Deeds

- 1. Public Land Survey T 57N R 32W G-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. W. CRAMPTON, in a field survey on OCTOBER 30, 19 81
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 POST - 13" YELLOW BIRCH S60W 40, 10" SUGAR MAPLE N30E 10, NOTHING FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 2" IRON PIPE FOUND AT THE INTERSECTION OF BLAZED AND PAINTED TREES SOUTH AND EAST OF CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 THE 2" IRON PIPE WITH 4" BRASS CAP WAS WITNESSED WITH P.K. NAILS NAILED TO:
12" MAPLE TREE N70W 16.13', 10" MAPLE TREE N40E 28.39',
10" MAPLE TREE S85W 24.03', 10" MAPLE TREE S44W 12.72'.

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. James M. Hubbell
Date 10/15/96

Signed by Robert W. Crampton
Surveyor's Michigan License No. 24591

Date OCTOBER 1, 1996