

SURVEY & REMONUMENTATION

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KEWEENAW - REMON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 57N R 32W
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

G-10

REGISTER'S OFFICE }
County of Keweenaw } SS
Received for Record, the 8th
day of November A.D. 1996
at 11:00 o'clock A.M., and Recorded
in Liber 1 of LCR
on page 173
Roberta Rosenbuser Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. W. CRAMPTON, in a field survey on JUNE 13, 1985
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10 W 1/4 CORNER SECTION 27 - SET POST - CEDAR 12 N70E 10, SPRUCE 18 S50W 14.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 W 1/4 CORNER 1 1/2" IRON PIN FOUND IN CONCRETE (DISTURBED)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 THE 1 1/2" IRON PIPE WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
UTILITY POLE N69W 84.91', UTILITY POLE N19E 146.41',
4" APPLE TREE N58E 16.73', 5" PIN CHERRY TREE S11W 104.62'.

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. [Signature]
Date 10/15/96

Signed by Robert W. Crampton

Date OCTOBER 1, 1996

Surveyor's Michigan License No. 2459