

MAR 19 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KEWEENAW - REMON  
(County)

Located in:

Corner Code #

REGISTER'S OFFICE }  
County of Keweenaw } SS  
Received for Record, the 8<sup>th</sup>  
day of November A.D. 1996  
at 11:00 o'clock A. M., and Recorded  
in Liber 1 of LCR  
on page 140  
Robert Rosenberg, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

- |                                      |   |            |   |            |             |
|--------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey                | T | <u>57N</u> | R | <u>32W</u> | <u>H-11</u> |
|                                      | T |            | R |            |             |
|                                      | T |            | R |            |             |
|                                      | T |            | R |            |             |
| 2. Property Controlling in Section   | S |            | T | R          |             |
|                                      | S |            | T | R          |             |
| 3. Miscellaneous Property in Section | S |            | T | R          |             |
|                                      | S |            | T | R          |             |
| 4. Lot No. _____, Recorded Plat      |   |            |   |            |             |
| 5. Private Claims                    |   |            |   |            |             |

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. W. CRAMPTON, in a field survey on JUNE 14, 1985, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11 N 1/4 CORNER - SET POST - SUGAR 10 S30E 23, MAPLE 10 N45W 31.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 N 1/4 CORNER - 1 1/2" IRON PIPE FOUND AT INTERSECTION OF FOUR FENCES NORTH, SOUTH, EAST & WEST OF CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 THE 1 1/2" IRON PIPE WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:  
5" Y. BIRCH TREE N29W 24.80', 10" OAK TREE S83E 23.5',  
4" BASSWOOD TREE S3E 16.42', 9" MAPLE TREE S39W 19.0'.

Ratified by Peer Group  
In accordance with P.A. 345  
Co. Rep. [Signature]  
Date 10/15/96

Signed by Robert W. Crampton  
Surveyor's Michigan License No. 24591

Date OCTOBER 1, 1996