

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Keweenaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>57N</u> R <u>32W</u>	<u>83</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>57N</u> R <u>32W</u>	<u>2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Jan 04 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B3) Quarter corner common to Sections 6 and 7. 1845 - Established by Douglas Houghton, Deputy Surveyor: East corr. btwn Sec. 6 & 7 ...36.75 Set post quarter section cor. fir 10 S50W 10 links, Sugar N50E 10 links. ...76.75 Section corner. Previous survey by John I. Haataja PS 19833 show that this corner was reestablished by single proportionate measurement to the original record between Section corners 2614.08' East and 2401.68' West. Mr. Haataja used the reestablished position to subdivide Section 6. A sketch of this survey is located at the offices of the former Lake Superior Land Company in Calumet, MI.
 (2-Sec. 7) East 1/16 corner between Sections 6 and 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B3) The original post and accessories were not recovered. Found no monumentation at the corner position. Monumented the reestablished corner position noted above by single proportionate measurement to the original record and to Mr. Haataja's measure between Section corners found 2613.39' East (2614.08 JIH measure) and 2401.05' West (2401.68' JIH measure).
 (2-Sec. 7) Established the corner midway and on the Section line between Quarter corner 1306.69' West and Section corner 1306.69' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Cedar N56E 25.2' mrkd "1/4S NBT" 7" Cedar S82E 7.1' do 9" Cedar S23E 11.3' do 4" Sugar N82W 9.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 10" Cedar S65E 8.4' mrkd "1/16S BT" 10" Cedar S15W 9.0' do 9" Cedar N67W 9.7' do 14" Spruce N25W 4.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/06

For the Michigan Department of Natural Resources, Office of Land and Facilities