

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Keweenaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>57N</u> R <u>32W</u>	<u>C3</u>
	T <u>57N</u> R <u>32W</u>	<u>A3</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

A3 Feb 25 2006
 C3 Feb 22 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3			●										
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

(C3) Section corner common to Sections 5-6-7-8. 1994 - Reestablished by John I. Haataja PS19833 and ratified by Keweenaw County Peer Group in accordance with P.A.345. Recorded in Liber 1 of LCR Page 126, Keweenaw County records.
 (A3) Corner common to Sections 6-7 T57N-R32W and Sections 1-12 T57N-R33W. 1993 - Remonumented by John I Haataja PS19833 and ratified by Keweenaw County Peer Group in accordance with P.A. 345 in 1994. Recorded in Liber 1 of LCR, Page 120, Keweenaw County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) Found the 1994 monument, a 1" iron pipe with brass cap, in good condition and at record bearing and distance from the remains of the 1994 witnesses as follows: R.Maple N30E 13.6' (rec. as 8" R.Maple N27E 13.50') with nearly overgrown blazes, large Aspen stump S80E 7.95' (rec. as 28" Aspen S85E 7.60'), Maple stump S18E 5.65' (rec. as 8" Red Pine S22E 5.55'), 4" R.Maple S50W 5.0' (rec. as 4" Red Maple S51W 5.38') with blazes and measuring nail. Left the monument in place and made new witnesses as described below.
 (A3) Found the 1993 monument, a 1" ID iron pipe with 4" brass cap, in good condition and at record bearing and distance from the 1993 witnesses recovered as follows: 7" Sugar S81W 16.8' (rec. as 5" H.Maple S80W 16.74') with overgrown blazes, 11" W.Birch N01E 29.4' (rec. as 12" W.Birch N01W 29.40') with overgrown blazes, 11" Sugar N51E 17.2' (rec. as 10" Poplar N51E 17.16') with overgrown blazes, 12" Poplar South 1.18' (rec. as 12" Poplar South 1.18') with old blazes (subsequently cut down by the undersigned to facilitate GPS observations). Left the monument in place and made 1 new witness tree as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) Found 1" I.pipe with 4" brass cap. Set measuring nails in: 6" Cedar S63E 31.9' mrkd "S8 NBT" 8" Cedar S30E 21.7' do 8" R.Maple N30E 13.6' old blazes * 4" R.Maple S50W 5.0' old blazes * Bearings are magnetic. Distances are horizontal and to nail in side of tree. * denotes 1994 NBT.	(A3) Found 1" Iron pipe with 4" brass cap. Set measuring nail in: 16" Maple S08E 21.7' mrkd "S7 NBT" 7" Sugar S81W 16.8' old blazes * 11" W.Birch N01E 29.4' do * 11" Sugar N51E 17.2' do * Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail in side of tree. * denotes 1993 NBT.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/06