

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Keweenaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>7</u> T <u>57N</u> R <u>32W</u>	<u>1</u>
	S <u>7</u> T <u>57N</u> R <u>32W</u>	<u>9</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

9 Feb 22 2006
 1 Jan 09 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (1-Sec. 7) West 1/16 corner between Sections 6 and 7. Not established in the original survey.
- (9-Sec. 7) East 1/16 corner, Section 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (1-Sec. 7) Established the corner 20 chains, proportionate to the original record, west of Quarter corner B3, 1306.70' East, and on the Section line between B3 and Section corner A3, 1094.36' West
- (9-Sec. 7) Established the corner midway and on a straight line between Center of Section 7 1348.56' West and Quarter corner C4 1348.56' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (1) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
6" Maple N16W 8.7' mrkd "1/16S BT"
4" Cedar N55E 20.2' do
8" Cedar S70E 32.7' do
6" Y.Birch S29W 19.4' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (9) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
12" Cedar N13E 18.6' mrkd "1/16S BT"
11" Cedar S60E 1.25' do
5" Hemlock S12W 22.9' do
10" Cedar N70W 0.75' do
Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/06

For the Michigan Department of Natural Resources, Office of Land and Facilities