

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

KEWEENAW COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw
(County)

Located In:

Corner Code #/

1. Public Land Survey

T 57N R 33W

T 57N R 33W

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

I-13
I-12 ✓

REGISTERED

County of Keeweenaw, MI

Created by _____ on the 20th

day of January, A.D. 1995

at 10:30 o'clock A.M. and Recorded

in Liber _____ of LCR

on page 135

Marilyn Wingquist
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Steven C. Hein, in a field survey on November 9, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I-13) SW Cor. Sec. 35: Set post corner of Sections 34 & 35 Sugar 7 N4E 28, Do 12 N25W 45 Original corner not found. No subsequent information of record.

(I-12) W $\frac{1}{4}$ Cor. Sec. 35: Set $\frac{1}{4}$ Section Corner Cedar 18 N60E 04, Do 15 S70W 23 Original corner not found. Old 1" pipe found lying by fence corner by C.E.Hein, P.S. in Sept., 1991 survey. Corner location checked and accepted in subsequent survey. 1 $\frac{1}{4}$ " pipe set for W $\frac{1}{4}$ cor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I-13) SW Cor. Sec. 35: Found NW Cor. Sec. 2, T56N-R33W (3/4" pin) Verified its position with 1/4 corners to West & South. Set SW Cor. Sec. 35 on line between NW. Cor. Sec. 2 and S $\frac{1}{4}$ Cor. Sec. 35, at 33.0' (50links Original record) distance from the NW Cor. Sec. 2, T56N-R33W.

(I-12) W $\frac{1}{4}$ Cor. Sec. 35: Found 1 $\frac{1}{4}$ " pipe, 16" A.G. at intersection of fences to North & East. Found witnesses with face blazes and side blazes with nail & tag #13034: 8" R.Maple N82°E 16.86'; 5" Aspen S59°E 8.33'; 3" R.Pine S86°W 5.86'; 6" R.Pine N15°W 5.74'

Ratified by Peer Group

In accordance with P.A. 345

Co. Rep. James M. Hult

Date 10/28/1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I-13) SW Cor. Sec. 35: Set 1" pipe with 4" Brass Cap stamped "KEWEENAW COUNTY REMONUMENTATION POINT" T57N-R33W, S34/S35 P.S. 32336 Witnesses with face blaze and side blaze with nail & tag #32336: 10" Triple H.Maple N19°E 52.55'; 4" Oak S67°E 22.34'; 6" H.Maple S02°E 24.78'; 5" Oak N64°W 5.03'.

(I-12) W $\frac{1}{4}$ Cor. Sec. 35: Replaced 1 $\frac{1}{4}$ " pipe with 1" pipe with 4" Brass Cap stamped "KEWEENAW COUNTY REMONUMENTATION POINT" T57N-R33W, 1/4, S34/S35, P.S. 32336. Witnesses as shown in section B above

Signed by Steven C. Hein

Date December 28

Surveyor's Michigan License No. 32336

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, MAY 28, 1971
REVISED MAY 24, 1975
REVISED JAN., 1983

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

