

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**KEWEENAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Keweenaw</u> (County)	Located In:	Corner Code <u>11</u>
1. Public Land Survey	T <u>57N</u> R <u>33W</u>	<u>K-13</u>
	T <u>57N</u> R <u>33W</u>	<u>J-13</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE
County of Keweenaw } SS
Received for Record, the 20th
day of January A.D. 1995
at 10:30 o'clock A.M., and Recorded
in Liber _____ of LCR
on page 134
Manly W. Wainwright
Register of Deeds

Register of Deeds Stamp & File Number

I, Steven C. Hein, in a field survey on November 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- (K-13) SE Cor. Sec. 35: Set post corner of Sections 35 & 36 Cedar 10 N35E 26, Fir 7 N6W 36 Original corner not found No subsequent information of record.
 - (J-13) S $\frac{1}{4}$ Cor. Sec. 35: Set $\frac{1}{4}$ Section post Sugar 7 N38E 11, Do 12 N38W 24 Original corner not found. $\frac{1}{4}$ " pin in conc., marked "57-R Sec 35 $\frac{1}{4}$ cor" (parts broken off) found in Sept., 1991 survey by C.E.Hein, P.S.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (K-13) SE Cor. Sec. 35: Found 1" pin in 24" diameter conc. 8" below road surface and 9.5' West of centerline. Found 1" pin (NE cor. Sec. 2, T56N-R33W) 6.59' East (Original record: 6.6') Accepted pin as found.
 - (J-13) S $\frac{1}{4}$ Cor. Sec. 35: Found $\frac{1}{4}$ " pin as described. Found witnesses with face blaze and side blaze with nail & tag #13034: 6" H. Maple N11°E 20.69'; 6" H. Maple S43°E 11.41'; 7" H. Maple S32°W 9.79'; 5" R. Maple N47°W 7.52'

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. James M. Hubbs
Date 10/28/1993

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- (K-13) SE Cor. Sec. 35: Due to size and extent of monument found, 1" pin in conc. was accepted and used. Unable to place remon. cap. Witnesses with face blaze and side blaze with nail & tag #32336: 12" Cedar N25°E 69.45'; 8" Cedar N83°E 40.41'; 10" Aspen S69°E 36.10'; 6" Twin Birch S34°E 89.39'
 - (J-13) S $\frac{1}{4}$ Cor. Sec. 35: Set 4" Brass Cap over $\frac{1}{4}$ " pin, stamped "KEWEENAW COUNTY REMONUMENTATION POINT" T57N-R33W, Sec 35, S1/4, P.S. 32336 Witnesses as shown in section B above.

Signed by Steven C. Hein Date December 28, 1993
Surveyor's Michigan License No. 32336

