

JAN 05 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw

(County)

Located In:

Corner Code #

1. Public Land Survey

T 57 R 33

K-7

T 57 R 33

L-7

T R

T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

S T R

REGISTER'S OFFICE

County of Keweenaw } SS

Received for Record, the 13th

day of December A.D. 1999

at 1:00 o'clock P.M., and Recorded

in Liber 1 of LCR

on page 216

James M. Pardini, Deputy

Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

I, James M. Pardini, in a field survey on 5/5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Two dots are marked at the intersection of row 7 and column L, and row 8 and column M.

A. Description of original monument and accessories and/or subsequent restoration:

(K-7) NW corner section 24 T57N-R33W 5" diameter Fir post set for section corner by Samuel W. Hill in 1845. U.S. Bearing Trees: 16" Yellow Birch N10°E 47 lks 12" Sugar S05°W 50 lks

(L-7) N 1/2 corner section 24T57N-R33W 2" diameter Maple post set for quarter section corner by Samuel W. Hill in 1846. U.S. Bearing Trees: 6" Hemlock S30°E 25 lks 22" Hemlock N03°W 18 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-7) Re-established section corner by double proportionate measure between the North 1/2 corner section 23-57-33 and NE section corner, section 24-57-33 East and West and the NE section corner section 14-57-33 and SE section corner section 26-57-33 North and South. (L-7) Re-established 1/2 corner by single proportionate measure between section corners East and West.

Ratified by Peer Group In accordance with P.A. 345 Co. Rep. James M. Pardini Date 12/7/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-7) Set 1"x36" iron pipe 24" in ground /w 4" brass cap marked "Keweenaw Co., Remonumentation Point".

8" Sugar Maple N14°W 6.11' 7" Sugar Maple N64°E 9.91' 8" Sugar Maple S05°E 14.78' 8" Red Maple S82°W 29.39'

(L-7) Set 1"x36" iron pipe 24" in ground /w 4" brass cap marked "Keweenaw Co., Remonumentation Point".

8" Sugar Maple N42°W 36.72' 6" Sugar Maple S34°W 42.24' 6" Sugar Maple N60°E 25.80' 8" Red Maple S40°E 7.26'

Signed by James M. Pardini Surveyor's Michigan License No. 32340

Date 12/7/99

