

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

KEWEENAW COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Keweenaw</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>57N</u> R <u>33W</u>	<u>K-11</u> ✓
	T <u>57N</u> R <u>33W</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE }
County of Keweenaw } SS
Received for Record, the 20th
day of January A.D. 1995
at 10:30 o'clock A.M., and Recorded
in Liber 1 of LCR
on page 133
Maude W. Winkler
Register of Deeds

Register of Deeds Stamp & File Number

I, Steven C. Hein, in a field survey on November 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- (K-11) NE Cor. Sec. 35: Set post Fir 4 inches diameter in level ground corner of Sections 25-26-35 & 36; Sugar 18 S45W 45, Y Birch 8 N70E 10. Original corner not found. Spike found in E gravel road fences N. & So., in Sept., 1991 survey by C.E.Hein, P.S. Spike replaced with 1/2" capped pin #13034, witnesses as noted below.
 - (K-12) E 1/4 Cor. Sec 35: Set post quarter Section corner; Cedar 10 S10E 15, Do 11 N71E 17. Original corner not found. 1/2" pipe in conc. found and accepted by C.E.Hein, P.S. in Sept., 1991 survey. Witnesses as noted below.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (K-11) NE Cor. Sec. 35: Found 1/2" capped pin #13034 2" B.G. in E gravel road. Found witnesses with face blaze and side blaze with nail & tag #13034: 7" Oak N34°E 33.57'; 6" Cedar S09°E 48.77'; 6" R.Pine S48°W 42.12'; 8" Oak N19°W 30.61'
 - (K-12) E 1/4 Cor. Sec. 35: Found 1/2" pipe in conc., 10" B.G. in E East/West gravel road & 22' West of E gravel road to South. Found witnesses with face blaze and side blaze with nail & tag #13034: 7" H.Maple N16°E 42.16'; 9" Basswood N52°E 47.28'; 5" Cedar S45°W 35.17'; 7" Cedar N39°W 22.73'

**Ratified by Peer Group
In accordance with P.A. 345**
Co. Rep. James M. Holth
Date 10/28/1993

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- (K-11) NE Cor. Sec. 35: Replaced capped pin with 4" Brass Cap stamped "KEWEENAW COUNTY REMONUMENTATION POINT" T57N-R33W, S26, S25, S35, S36, P.S.32336. Witnesses as shown in section B above.
 - (K-12) E 1/4 Cor. Sec. 35: Replaced 1/2" pipe with 4" Brass Cap stamped "KEWEENAW COUNTY REMONUMENTATION POINT" T57N-R33W, 1/4, S35/S36 P.S.32336. Witnesses as shown in section B above.

Signed by Steven C. Hein Date December 28
Surveyor's Michigan License No. 32336

