

JAN 05 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw
(County)

Located in:

Corner Code #

- 1. Public Land Survey

T 57 R 33	M-7 ✓
T 57 R 33	M-8
T R	
T R	
- 2. Property Controlling in Section

S T R	
S T R	
- 3. Miscellaneous Property in Sec.

S T R	
S T R	

REGISTER'S OFFICE }
 County of Keweenaw } SS
 Received for Record, the 1314
 day of December A.D. 19 99
 at 1:00 o'clock P.M., and Recorded
 in Liber 1 of LCR
 on page 214
Julie Carlson, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, James M. Pardini, in a field survey on 9/28, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 (M-7) NE Cor Sec 24, T57N-R33W, Wood post set by Austin Burt in 1845.
 U.S. Bearing Trees: 10" Sugar S42°W 27 lks
 30" Hemlock N59°W 18 lks
 Samuel W. Hill DS 18" Sugar S40°E 37 lks
 Subdivision T57N-R33W 12" Cedar N20°E 14 lks
 (M-8) East 1/4 corner section 24, T57N-R33W, wood post set for quarter section corner by Austin Burt DS in 1845. U.S. Bearing Trees:
 10" Maple S28°W 18 lks
 12" Pine N38°E 18 lks

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (M-7) Calumet and Hecla Mining Co., records indicate an iron pipe set in concrete. Found and noted by Walt Kline in 1953. Found and accepted iron pipe in concrete 6" below grade (Disturbed).
 (M-8) Re-established 1/4 corner by single proportionate measure between section corners North and South.

Ratified by Peer Group
 In accordance with P.A. 345
 Co. Rep. James M. Pardini
 Date 12/7/99

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (M-7) Set 1"x36" iron pipe /w 4" brass cap marked "Keweenaw Co., Remonumentation Point" 8" below grade at base of disturbed pipe.
 14" Red Pine N48°E 45.40'
 6" Aspen S13°E 56.18'
 Utility pole S46°W 37.68'
 Utility pole N11°W 122.68'
 (M-8) Set 1"x36" iron pipe /w 4" brass cap marked " Keweenaw Co., Remonumentation Point" Located at corner of clear cut.
 10" Aspen N05°W 11.34' 18" White Birch N78°E 48.76'
 8" Red Maple N50°E 19.57'
 6" Red Maple N55°E 42.75'

Signed by James M. Pardini
 Surveyor's Michigan License No. 32340

Date 12/7/99

