

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Keweenaw
(County)

Located In:

Corner Code #

REGISTER'S OFFICE, SS
County of Keweenaw

Received for Record, the 4th
day of December A. D. 1998
at 11:00 o'clock A. M., and Recorded
in Liber 1 of LCR
on page 182
Marilyn Wingard
Register of Deeds State of Michigan

- | | | | | | |
|--------------------------------------|---|------------|---|------------|--------------|
| 1. Public Land Survey | T | <u>58N</u> | R | <u>27W</u> | <u>G-3</u> |
| | T | ___ | R | ___ | ___ |
| | T | ___ | R | ___ | ___ |
| | T | ___ | R | ___ | ___ |
| 2. Property Controlling in Section | S | <u>10</u> | T | <u>58N</u> | R <u>27W</u> |
| | S | ___ | T | ___ | R ___ |
| 3. Miscellaneous Property in Section | S | ___ | T | ___ | R ___ |
| | S | ___ | T | ___ | R ___ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Ronald S. Haataja, in a field survey on September, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (G-3) NW Corner Section 10, T58N-R27W
80.00 Set Post Corner of Sections 3,4,9,&10 on bare rock. References: W. Pine 6" S71°E 35 lks.
Aspen 4" S17°W 42 lks.
- (3) N1/16 Corner between Sections 10 & 9, T58N-R27W
Not set in original survey.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (G-3) NW Corner Section 10, T58N-R27W
1-1/2" Iron Pipe found next to square wood post with C&H tag. Accepted the pipe as the corner.
- (3) N1/16 Corner between Sections 10 & 9, T58N-R27W
Set 1" Pipe flush at found location of wood post with C&H tag.

Rated by Peer Group
In accordance with P.A. 345
Co. Rep. James M. Hobbs
Date 12/3/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (G-3) NW Corner Section 10, T58N-R27W
Witnesses: 12" W. Pine N52°W 13.65', 30" W. Pine S07°E 28.40',
6" Spruce N05°E 7.20', 12" Cedar N54°E 23.20'.
- (3) N1/16 Corner between Sections 10 & 9, T58N-R27W
Witnesses: 4" Balsam w/tag S57°W 8.50', 14" Cedar N85°W 22.15',
6" Balsam N36°E 12.75', 6" Balsam S21°E 16.90',

Signed by Ronald S. Haataja

Date October 28, 1998

Surveyor's Michigan License No. 39478