

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER'S OFFICE

For corners in

KEWEENAW  
(County)

Located In:

Corner Code #

County of Keweenaw } SS

Received for Record, the 7<sup>th</sup>  
day of December A.D. 2000  
at 10:30 o'clock A M., and Recor:  
in Liber 2 of LCR  
on page 8

Julie Carlson, Deputy  
Register of

Register of Deeds Stamp & File Number

1. Public Land Survey T 59N R 28W C12  
T 59N R 28W C13  
T 58N R 28W C1 ✓  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ SURVEY &  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ REMONUMENTATION  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ FEB 07 2001

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_ SECTION

I, R. W. CRAMPTON, in a field survey on November 2000, ~~19~~  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found  
as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-12: Post; W. Birch 9" S47°W 17 links, W. Birch 6" N76°E 21 links (no evidence found).

C-13: Post; Aspen 8" N52°E 24 links, Aspen 6" N69°W 24 links (no evidence found).

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-12: Found 1" steel pin in concrete, the position of which was in agreement with historical perpetuation of this corner. Monument accepted as found (see LCRC filed in Liber 1, P.16 on 02/03/82).

C-13: Found 1" steel pin in 2'x2' square concrete pad with Sections 31 & 32 T59N, R28W and Sections 5 & 6, T58N, R28W written in the concrete. Old red blaze lines found running West and South of corner position. Monument accepted as found.

Ratified by Peer Group  
In accordance with P.A. 345  
Co. Rep. [Signature]  
Date 12/01/00

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-12: Found 1" steel pin capped with a 4" diameter Keweenaw County Remonumentation Point brass cap and witnessed with a survey tag, stamped PS 24591, nailed to: 9" White Birch tree N26°W 20.44 feet, 10" White Birch tree S76°E 3.56 feet, 8" Maple tree S21°W 14.68 feet, twin 4" Maple tree S87°W 22.27 feet.

C-13: Found 1" steel pin capped with a 4" diameter Keweenaw County Remonumentation Point brass cap and witnessed with a survey tag, stamped PS 24591, nailed to: 8" Birch tree N05°E 18.48 feet, 5" Maple tree N60°E 22.98 feet, 14" Pine tree S25°E 24.13 feet, 12" Pine tree S30°W 12.24 feet.

Signed by R. W. Crampton Date Dec. 1, 2000  
Surveyor's Michigan License No. 24591

98-28

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	10	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

