

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970 REGISTER'S OFFICE

For corners in

Keweenaw  
(County)

Located In:

Corner Code #

County of Keweenaw } SS

Received for Record, the 4th  
day of December A. D. 1998  
at 11:00 o'clock A. M., and Recorded  
in Liber 1 of LCR  
on page 186  
Marilyn Wikquist  
Register of Deeds Stamp & File Number

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>58N</u> R <u>29W</u> | <u>C-11</u> |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John I Haataja, in a field survey on 11/11, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-11 Northwest corner of Section 32 T58N-R29W  
Wood post was set for corner of Section 29, 30, 31, & 32 by Samuel Hill in 1847.  
Reference: 6" Yellow Birch S18°W 21 lks  
16" Hemlock N30°E 43 lks  
2" pipe found and accepted by John Haataja, P.S. in a survey dated June 1992.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 2" pipe flush with ground  
18" Yellow Birch with C&H tags S82°E 9.44'  
14" Cedar S16°W 34.80'  
12" R. Maple S89°W 13.64'  
4" Cedar N23°E 14.92'

Ratified by Peer Group  
In accordance with P.A. 345  
Co. Rep. James M. Hall  
Date 12/3/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 NW corner of Section 32 T58N-R29W  
Grouted a 4" brass cap stamped Keweenaw County Remonumentation point into existing 2" pipe.  
18" Yellow Birch S82°E 9.44'  
14" Cedar S16°W 34.80'  
12" R. Maple S89°W 13.64'  
4" Cedar N23°E 14.92'



Signed by John I. Haataja Date 12/1/98  
Surveyor's Michigan License No. 19833