

SURVEY & REMONUMENTATION

MAR 19 1997

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

REGISTER'S OFFICE }
County of Keweenaw } SS
Received for Record, the 9th
day of December A.D. 19 96
at 1:00 o'clock P.M., and Recorded
in Liber 1 of LCR
on page 158
Dorinda Rosenberger Deputy
Register of Deeds

<u>Keweenaw</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>58N</u> R <u>29W</u>	<u>G-1</u>
	T <u>58N</u> R <u>29W</u>	<u>E-1</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John I. Haataja, in a field survey on September 15, 19 96
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <p>G-1 NE cor. Sec. 4
Wood Post
Cedar 14" N 51° E 19 lks.
Cedar 8" N 30° W 28 lks.</p> | <p>E-1 NW cor. Sec. 4
Wood Post
Sugar 7" N 12° E 26 lks.
Sugar 7" N 35° W 30 lks.</p> |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|---|
| <p>G-1 Found original B.T. Cedar NE
with scribes laying down.
Found other BT stump.
Re-established corner from BTs.</p> | <p>E-1 Found 2 Cedar BT's not original.
Old C&H notes call for square
Cedar for corner.
Re-established corner from Cedar
BTs.</p> |
|---|---|

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. [Signature]
Date 12/6/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>G-1 NE corner Sec. 4
1" pipe with brass cap
15" Cedar N 29° E 21.02'
14" Cedar S 16° E 13.68'
10" Cedar S 66° W 14.92'
28" Cedar N 28° W 12.76'</p> | <p>E-1 NW corner Sec. 4
1" pipe with brass cap
14" Cedar N 31° W 5.15'
12" Cedar N 50° E 3.31'
9" Maple S 60° W 11.35'
8" Maple S 10° W 7.85'</p> |
|--|---|



igned by [Signature] Date November 20, 1996
urveyor's Michigan License No. 19833