

**SURVEY & REMONUMENTATION**

**JAN 21 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Keweenaw \_\_\_\_\_  
(County)

Located In:

Corner Code **#**

1. Public Land Survey

T 58N R 29W  
 T 58N R 29W

G-12  
 MC 12

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE

County of Keweenaw 1 SS

Received for Record the 30<sup>th</sup>

day of December A.D. 19 97

at 10:00 o'clock A.M. and Recorded

in Liber 1 of LCR

on page 177

*Julie Carlson* Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

I, John Haataja, in a field survey on 11/7, 19 97

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12 Wood post set in 1847.  
 Spruce 8" N10°E 21 LKS

MC 12 Wood post set in 1847  
 W. Pine 16" N27°W 48 LKS  
 Cedar 10" S40°E 80 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


G-12 No evidence of original corner found  
 Set 1/4 corner midway between the NW corner and the SW corner of Section 34.

MC 12 No evidence of original corner found.  
 Reestablished meander corner on Section line between NW corner and the SW corner of Section 34. at high watermark.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 Set 1" pipe with brass cap  
 6" Red Maple S73°W 21.64'  
 13" Red Maple N27°W 30.75'  
 10" Red Maple N77°E 26.92'  
 10" Red Maple S70°E 33.56'

MC 12 Set 1" pipe with brass cap  
 5" Cedar N34°W 6.10'  
 8" Tamarack N36°E 9.76'  
 6" Tamarack N62°E 47.03'  
 4" Tamarack S30°W 13.12'



Signed by *John Haataja*  
 Surveyor's Michigan License No. 19833

Date 12/30/1997

