

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Keweenaw County

Located in:

Corner Code #

- 1. Public Land Survey T58N R30W
- T58N R30W
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

A13
C13

- 4. Lot No. , Recorded Plat
- 5. Private Claims

REGISTER'S OFFICE } SS
 County of Keweenaw }
 Received for Record, the 4th
 day of December A. D. 1998
 at 11:02 o'clock A. M., and Recorded
 in Liber 1 of LCR
 on page 197
Mailyn Wierquist
 Register of Deeds
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A13: SW Corner Section 31: From original notes: North on East side of Sec. 1, T57N, R31W; 80.00 Set post Corner to Townships 57 & 58 N. between Ranges 30 & 31 West; Y. Birch 14 N68E 15 lks.; Sugar 10 S53W 12 lks. No evidence of original corner or accessories found.

C13: Corner between Sections 31 & 32: From original notes: East on South side of Sec. 31, T58N, R30W: 76.75 Set post Corner to Secs. 31 & 32; Birch 12 N19E 36 lks.; B. Oak 14 N26W 22 lks.. No evidence of original corner or accessories found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A13: SW Corner Section 31: Found 1" square pin in concrete as recorded J. I. Haataja, P.S. 19833 in Liber 1 of L.C.R.C., Page 58. Witnesses of said record: 10" Maple N65°E 8.69'; 10" Maple N26°E 16.71'; 10" Maple N75°W 26.15'; 5" Ironwood S38°W 24.17'

C13: Corner between Sections 31 & 32: Having found the recorded Southwest and Southeast Corners of the Township, all the Section corners between were set on a true parallel of latitude established by using the secant method. Positions fit well with found evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A13: Accepted 1" Square pin in concrete, No Brass Cap set
Witnesses(As recorded):
10" Maple N65°E 8.69'
10" Maple N26°E 16.71'
10" Maple N75°W 26.15'
5" Ironwood S38°W 24.17'

C13: Set 4" Brass Cap stamped for corner on 1" pipe, 7" A.G.
Witnesses:
12" H. Maple N67°E 17.25'
6" H. Maple S42°E 16.67'
8" H. Maple S61°W 10.60'
6" H. Maple N65°W 22.91'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by *Steven C. Hein*

Date 11/14/98

Surveyor's Michigan License No. 32336