

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Keweenaw County

Located in:

Corner Code #

- 1. Public Land Survey T58N R30W
- T58N R30W
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

E13  
G13

- 4. Lot No. , Recorded Plat
- 5. Private Claims

REGISTER'S OFFICE } SS  
 County of Keweenaw }  
 Received for Record, the 4<sup>th</sup>  
 day of December A. D. 1998  
 at 11:00 o'clock A. M., and Recorded  
 in Liber 1 of LCR  
 on page 198  
Marilyn Wierquist  
 Register of Deeds  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E13: Corner between Sections 32 & 33: From original notes: East on South side of Sec. 32, T58N, R30W; 80.00 Set post Corner to Secs. 32 & 33; Sugar 12 N75E 14 lks.; do 8 N72W 35 lks. No evidence of original corner or accessories found.

G13: Corner between Sections 33 & 34: From original notes: East on South side of Sec. 33, T58N, R30W; 80.00 Set post Corner to Secs. 33 & 34; Sugar 14 N68E 46 lks.; do 7 N57W 17 lks. No evidence of original corner or accessories found.

Ratified by Peer Group  
 In accordance with P.A. 345  
 Co. Rep. [Signature]  
 Date 12/3/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E13: Corner between Sections 32 & 33: Having found the recorded Southwest and Southeast Corners of the Township, all the Section corners between were set on a true parallel of latitude established by using the secant Method. Position fits well with found evidence.

G13: Corner between Sections 33 & 34: Having found the recorded Southwest and Southeast Corners of the Township; all the Section corners between were set on a true parallel of latitude established by using the secant method. Positions fit well with found evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E13: Set 4" Brass Cap stamped for corner on 1" pipe, 4" A.G.  
 Witnesses:  
 5" H. Maple N01°E 19.36'  
 10" H. Maple N63°E 22.21'  
 7" H. Maple S48°E 16.69'  
 10" H. Maple N76°W 7.57'

G13: Set 4" Brass Cap stamped for corner on 1" pipe, 2" A.G., 11.5' No. of Power line  
 Witnesses:  
 9" H. Maple N03°E 28.50'  
 12" Cedar N50°E 52.78'  
 40" Cedar stump N79°E 44.92'  
 P.K. nail in rock face S86°W 37.44'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by [Signature]  
Surveyor's Michigan License No. 32336

Date 11/14/98