

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in:

Keweenaw County Located in: Corner Code #
1. Public Land Survey T58N R30W T58N R30W T T R T R R S T R S T R S T R
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. , Recorded Plat
5. Private Claims

113 K13

REGISTER'S OFFICE County of Keweenaw Received for Record, the day of December at 11:00 o'clock A.M., and Recorded in Liber 1 of LCR on page 199 Register of Deeds

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Numbers 1-36 are placed in the grid cells.

A. Description of original monument and accessories and/or subsequent restoration:

113: Corner between Sections 34 & 35: From original notes: East on South side of Sec. 34, T58N, R30W; 80.00 Set post Corner to Secs. 34 & 35; Birch 12 N19E 7 lks.; Sugar 7 N55W 48 lks. No evidence of original corner or accessories found.

K13: Corner between Sections 35 & 36: From original notes: East on South side of Sec. 35, T58N, R30W: 80.00 Set post Corner to Secs. 35 & 36; Sugar 10 N62E 31 lks.; do 8 N10W 24 lks. No evidence of original corner or accessories found.

Ratified by Peer Group In accordance with P.A. 345 Co. Rep. Date 12/3/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

113: Corner between Sections 34 & 35: Having found the recorded Southwest and Southeast Corners of the Township, all the Section corners between were set on a true parallel of latitude established by using the secant Method. Position fits well with found evidence.

K13: Corner between Sections 35 & 36: Having found the recorded Southwest and Southeast Corners of the Township, all the Section corners between were set on a true parallel of latitude established by using the secant method. Positions fit well with found evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

113: Set 4" Brass Cap stamped for corner on 1" pipe, 8" A.G., 10' No. of Power line Witnesses: 10" H. Maple N40°E 49.82' 7" Oak S39°E 58.87' Util. Pole S64°W 14.23' 14" H. Maple N33°W 50.16'

K13: Set 4" Brass Cap stamped for corner on 1" pipe, 4" A.G., 9' No. of Power line Witnesses: 8" H. Maple N41°E 48.80' 16" H. Maple S26°E 49.68' 13" H. Maple S27°W 55.07' 9" H. Maple N39°W 36.92'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein

Date 11/17/98

Surveyor's Michigan License No. 32336