

DEC 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw County Located in: Corner Code #

1. Public Land Survey		T58N	R30W	M13
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	
4. Lot No.				, Recorded Plat
5. Private Claims				

REGISTER'S OFFICE SECTION
County of Keweenaw 55
Received for Record, the 4th
day of December A. D. 1998
at 11:00'clock A. M., and Recorded
in Liber 1 of LCR
on page 200
Marilyn Wignat
Register of Deeds
Register of Deeds Stamp & File Number

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M13: SE Corner Section 36: From original notes: East on South side of Sec. 36, T58N, R30W; 80.00 Set post Corner to Townships 57 & 58 North between Ranges 29 & 30 West. No evidence of original corner or accessories found.

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. *James M. Kuhl*
Date 12/3/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M13: SE Corner Section 36: Found 1 1/4" pipe as recorded by J. I. Haataja, P.S. 19833 in Liber 1 of L.C.R.C., Page 82. Witnesses of said record: 12" Maple N37°E 20.10'; 12" Maple N86°E 25.58'; 8" Maple S43°E 50.55'; P.P. South 14.78'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M13: Replaced 1 1/4" pipe with Brass Cap stamped for corner, 2" A.G.
Witnesses (checked):
13" H. Maple N35°E 20.08'
12" Maple stump N82°E 25.55'
7" Maple stump S47°E 50.75'
Util. Pole S02°E 14.77'
New Witnesses:
9" H. Maple S33°E 43.08'
7" Ironwood S60°W 66.03'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by *Steven C. Hein*
Surveyor's Michigan License No. 32336

Date 11/14/98