

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KEWEENAW  
(County)

Located In:

Corner Code #

REGISTER'S OFFICE

County of Keweenaw

SS

Received for Record, the 9th  
day of November A.D. 2000  
at 10:40 o'clock A M., and Recorded  
in Liber 2 of LCR  
on page 5

Jim Carlson, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

1. Public Land Survey T 58N R 31W 13  
T R  
T R  
T R
2. Property Controlling S T R  
in Section S T R
3. Miscellaneous S T R  
Property in Section S T R

FEB 07 2001

SECTION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, R.W. CRAMPTON, in a field survey on August 15, 2000, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

*I-3: Post; Spruce 8" N51°E 17 links, White Birch 12" S48°W 16 links (no evidence found)*



**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

*I-3: MDOT Right-of-Way map for Highway M-26, sheet 18, shows the Section corner as monumented.*

*Plat of Survey for part of Government Lot 1, Section 10, drawn by C.E. Hein, PLS No. 13034, dated 9-84, shows the Section corner as monumented with a 1" pin and witnessed as follows: 16" Oak N11°E 23.26 feet, 10" White Birch N60°E 36.86 feet.*

*Crampton survey crew recovered a 3/4" iron pipe at the corner position during a survey within Government Lot 1, Section 10, and accepted the monument as found.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

*I-3: The found 3/4" iron pipe was left in place and the following witnesses were observed: 10" White Birch N58°E 37.43 feet, 9" Maple S82°E 47.54 feet, 5" twin Maple S33°E 26.47 feet, 17" Oak N13°E 24.02 feet; all witnesses tagged LLS 19833. East edge of M-26 bituminous surface lies Westerly 50 ± feet.*

Ratified by Peer Group  
in accordance with P.A. 345  
Co. Rep. [Signature]  
Date 12/04/00

Signed by [Signature]  
Surveyor's Michigan License No. 24591

Date Nov. 6, 2000