

MAR 29 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

Keweenaw County	Located in:	Corner Code #
1. Public Land Survey	T58N R31W	M13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

REGISTER'S OFFICE, SS
County of Keweenaw }
Received for Record, the 12th
day of March A. D. 1999
at 12:00 o'clock P. M., and Recorded
in Liber 1 of LCR
on page 205
Marilyn Wingard
Register of Deeds
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Steven C. Hein, in a field survey on October 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M13: SE Corner Section 36: From original notes: North on East side of Sec. 1, T57N, R31W; 80.00 Set post Corner to Townships 57 & 58 N. between Ranges 30 & 31 West: Y. Birch 14 N68E 15 lks.; Sugar 10 S53W 12 lks. No evidence of original corner or accessories.

Date: 12/3/98
Co. Rep. [Signature]
In accordance with P.A. 345
Ratified by Peer Group

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M13: SE Corner Section 36: Found 1" square pin in concrete as recorded by J. I. Haataja, P.S. 19833 in Liber 1 of L.C.R.C., Page 58. Witnesses of said record: 10" Maple N65°E 8.69'; 10" Maple N26°E 16.71'; 10" Maple N75°W 26.15'; 5" Ironwood S38°W 24.17'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M13: Accepted 1" Square pin in concrete,
No Brass Cap set
Witnesses(as recorded)
10" Maple N65°E 8.69'
10" Maple N26°E 16.71'
10" Maple N75°W 26.15'
5" Ironwood S38°W 24.17'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein

Date 3/10/99

Surveyor's Michigan License No. 32336