

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw
(County)

Located In: 58N 32W

Corner Code # C-13

- | | | | | | | |
|---------------------------------------|---|------------|---|-------------|-------|-------|
| 1. Public Land Survey | T | <u>58N</u> | R | <u>C-13</u> | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | | | | |
| 5. Private Claims _____ | | | | | | |

REGISTER'S OFFICE }
County of Keweenaw } SS 15th
Received for Record, the 15
day of December A.D. 1994
at 3:00 o'clock P. M., and Recorded
in Liber 1 of LCR
on page 119
Marilyn W. Haggart
Register of Deeds

Register of Deeds Stamp & File Number

I, John I. Haataja, in a field survey on October 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


C-13 Southeast Corner of Section 31, T58N-R32W
Original Notes: Wood Post
Sugar 8" N 69° E 15 lks.
Fir 8" N 36° W 40 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Southeast Corner of Section 31, T58N-R32W
No trace of original post.
Re-established corner from natural feature calls and old line blazes.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. Donald H. Hubbl
Date 11/16/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Southeast corner of Section 31, T58N-R32W
Set a 1" pipe with brass cap as a careful and faithful re-establishment of the position of the original corner.
6" R. Maple N 57° E 6.03'
14" H. Maple S 68° E 17.82'
5" H. Maple S 16° E 10.61'
6" H. Maple N 87° W 19.76'

Signed by John I. Haataja

Date November 22, 1994

Surveyor's Michigan License No. 19833